



SAFETY TOOLBOX TALK

Ref:	050	Author:	D Bibby	Date:	07.02.2024
Topic:			Plant & Equipment General		

This briefing is not intended to tell you how to do your jobs, it is designed to help keep you safe. We want everybody to be able to return home safely to their family and friends at the end of each day.

Plant and equipment can be mobile or static equipment used on construction sites, typical examples of plant and equipment used on construction sites are:-

- Excavators
- Dumper Trucks
- Cement Mixers
- Rollers
- Generators

Plant and equipment should only ever be used by persons that have been fully trained and deemed as competent to use the equipment, plant being operated by persons with a lack of knowledge of its capabilities means only one thing **DISASTER**.

Things to consider prior to operating plant.

Has an inspection been carried out, if not then ensure that this is done prior to its first use on that day, this should be recorded and kept with the machine.

Has the working area been segregated to avoid any unauthorised access.

Is a Banksman needed for the task in hand, if so ensure that the selected Banksman has been trained and is competent.

Am I using the correct plant for the task in hand? The plant should be selected to best suit the job if you do not use the correct equipment then you could be putting the plant under pressure causing it to malfunction and potentially injure someone.

Ensure that other operatives on site are aware of the dangers with contact with machinery, operatives should make visual contact with the machine driver before entering the danger zone, if the driver does not spot you then be patient and keep trying to gain his attention.

Discussion Points

Have you considered any risks to other people nearby when using plant and equipment?

Is there anything that could prevent that risk to other people?