

Risk Assessment No: WP-005				Task: Cyclones & EvoWash Sand Plant — Operation, Apex/Spigot Change							
Prepared By: Derick Bibby				Date: 02.08.2026			RA Review Date: 01.08.2027				
				Reviewed By: Lee Hardy			Date: 02.08.2026				
PPE: Safety Footwear, High Visibility Jacket, High Visibility Trousers, Hard Hat, Gloves, Ear Defenders, Mask, Eye Protection											
Hazard	Persons at Risk	L	S	R	Control Measures				L	S	R
Fall from cyclone tower or apex-access platform	Maintenance	3	5	15	- Fixed ladder with cage and rest platforms; guardrails on all access levels. - Rated harness anchored to designated point during apex/spigot change. - Rescue plan and second person present for all tower work. - No work at height in winds > 25 mph, lightning, or heavy rain.				1	5	5
Release of stored slurry / abrasive discharge on cyclone opening	Maintenance	4	3	12	- Isolate feed pump, close upstream valve, and drain cyclone before opening. - Face-shield and chemical-resistant coveralls worn. - Confirm zero pressure at gauge before releasing camlock or bolted joint. - Do not stand directly below apex — position beside line of discharge.				1	3	3
Contact with moving parts (drives, drums, agitators, augers)	Operator Maintenance Contractors	4	5	20	- Fixed guards to BS EN ISO 14120 secured with tooled fasteners. - No guard removed unless the machine is locked off in accordance with FoxSafe Isolation & Lock Out Procedure. - Emergency stops and pull-cord trip wires within reach; tested weekly. - Daily start-up checklist CL-WP-01 confirms all guards in place before running. - No loose clothing, jewellery or long hair uncovered.				1	5	5
Manual handling of screen media, cloths, cyclone parts, hoses	Maintenance Operator	4	3	12	- Task-based manual handling assessment for screen cloths, cyclone apex and filter-press cloths. - Mechanical lifting (chain block, telehandler, MEWP with man-basket) for loads > 20 kg. - Two-person lift protocol for awkward items. - LOLER-inspected lifting accessories only.				2	2	4
Entanglement — drums, drive shafts, couplings, take-up assemblies	Operator Maintenance	4	5	20	- Fixed guards on all drums, drives, couplings and take-up assemblies. - Belt-tracking adjusted from external take-up handles only. - Full LOTO before removing a guard, freeing a jammed belt or cleaning drums. - Signage “Guard must be in place before start” at each drum.				1	5	5
Noise exposure ≥ 85 dB	All plant personnel	4	3	12	- Noise survey identifies zones ≥ 85 dB — mandatory hearing protection signage. - Ear defenders SNR ≥ 27 dB issued and worn in mandatory zones.				2	3	6

					• Audiometry health surveillance for staff regularly on the plant footprint. • Noise-reducing enclosures maintained where fitted; damaged panels reported.			
Exposure to respirable crystalline silica (RCS) and other dusts	Operator Picking staff Loader driver	4	4	16	• Plant runs wet — spray bars on scalping and sizing screens for suppression. • Water suppression at feed hopper and stockpile transfer points. • FFP3 mask when dry-handling filter cake or working downwind of dust sources. • Air-conditioned cabs with positive-pressure filtered air on all mobile plant. • Personal RCS monitoring on rolling programme under health surveillance. • No dry-sweeping — vacuum or damp-down only.	2	4	8