

## ENVIRONMENTAL PROCEDURES PLAN

This Environmental Procedures Plan details the arrangements and procedures that we will use to help implement the Fox Group Environmental Management Policy and ensure compliance with current Environmental Legislation.

|                               |            |
|-------------------------------|------------|
| <b>Document Reference</b>     | FGEPP      |
| <b>Revision</b>               | 1.1        |
| <b>Author</b>                 | Lee Hardy  |
| <b>Approved by</b>            | Paul Fox   |
| <b>Date of Implementation</b> | 01.09.2020 |
| <b>Date of next review</b>    | 31.08.2026 |

## CONTENTS

|                                                   | <b>Page</b> |
|---------------------------------------------------|-------------|
| <b>Air Pollution</b>                              | 2           |
| <b>Environmental Spills</b>                       | 4           |
| <b>Contaminated Land</b>                          | 7           |
| <b>Ecology, Archaeology and Cultural Heritage</b> | 9           |
| <b>Noise and Vibration</b>                        | 11          |
| <b>Statutory Nuisance</b>                         | 13          |
| <b>Traffic Management</b>                         | 15          |
| <b>Waste Management</b>                           | 17          |

## **AIR POLLUTION**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of any specific procedures with regards to air pollution.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site/Location Manager**

- Overall responsibility for air pollution control on site
- Develop section of the Environmental Management Plan to include air pollution control
- Ensure everyone abides by air pollution control guidelines
- Liaise with the Environmental Manager for all air pollution control issues

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan regarding the control of air pollution
- Ensure all staff comply with the air pollution control procedures

### **PROCEDURES**

#### **Operational Control Guidelines**

1. Any requirements for air quality monitoring must be identified prior to the commencement of any works.
2. All activities which may cause air pollution should be highlighted and specific risk assessments and safe systems of works should be prepared.
3. All operations are to be carefully planned and managed to ensure that impacts are kept to a minimum.
4. All plant and equipment will be chosen and serviced regularly to minimise emissions.
5. Where air monitoring is carried out, all records will be retained for a minimum period of 12 years.
6. All permanent and temporary employees, including sub-contractors and suppliers, will be made aware of their responsibilities to ensure that no air pollution incidents occur.
7. In the event of an air pollution incident, the Emergency Control Procedures outlined below will be followed.

## **Emergency Control Procedures**

1. In the event that excessive dust is arising from operations on site due to plant or traffic movements, then damping down of the roads and surrounding area shall be used to control the dust. Road sweepers shall also be used to keep roads clean and tidy where appropriate.
2. If the problem persists it may be necessary to install wheel-washing systems.
3. Where dust is arising from excavations, water shall be applied across the working area.
4. Where dust is arising from stockpiles of materials, water shall be applied to the stockpile, or the stockpiles should be sheeted.
5. Care shall be taken in both instances where water is being applied to the soil to prevent excessive run-off causing a further pollution incident, or a safety hazard due to the weakening of the ground.
6. If any item of plant is releasing excessive emissions through its exhaust, it should be turned off, returned to the hire firm and replaced with better quality plant.
7. Where emissions are becoming a problem during cutting the method of working will be changed to use damping or extractive techniques.
8. Should any excessive odours arise from storage areas including fuel, chemicals and waste the cause should be investigated and changes made to storage arrangements.
9. Waste must be regularly collected and removed from site to prevent odour emissions.

## **ENVIRONMENTAL SPILLS**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to environmental spillages. It is the responsibility of all personnel to prevent spills through appropriate material storage and handling practices but should these controls fail, this procedure is needed to provide guidance on:

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site/Location Manager**

- Overall responsibility for prevention and control of potential spillages on site
- Develop section of the Environmental Management Plan to include prevention and control spillages
- Liaise with the Environmental Manager.

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan regarding the prevention and control of spillage issues
- Ensure all staff comply with the guidelines

### **PROCEDURES**

Once the safety risks of the spilt product have been assessed, the following guidance to mitigate the spill should be considered along with the specific circumstances of the spill, before deciding how best to stop, contain and recover the spillage.

#### **Stop the Leak at the Source**

Following assessment of safety risks of the material, consider actions required to control the source of the spill this will include:

#### **Contain the Spill**

Identify proximity of sensitive receptors including the workforce, the surrounding community or the river. Also consider the location of ignition sources or incompatible chemicals that may increase the risks presented by the spill.

Contain the spill by using absorbent material from the appropriate spill kit

Oil and Fuel Spill Kits – are to be used for diesel, fuel, unleaded petrol, hydraulic oils, grease and other petroleum based lubricant spills. They include oil absorbent booms, pillows and pads,

Some options for containing a spill include:

- a. Creating an earthen perimeter bund or using oil absorbent booms to act as a barrier;
- b. Preventing access into stormwater drains by:
  - i. Using drain covers over pits (drain covers found in all small oil spill kits.);
  - ii. Plugging the stormwater pipe using inflatable fenders;
- c. Use of absorbent pads around the edge of the hydrocarbon spill;
- d. Use of hydrophobic booms to restrict the flow of liquid and keep it pooled within the booms;
- e. Redirecting the flow of material to an area that poses less safety or environmental risk;
- f. Identify any other reasonable actions that may improve containment.
  - As a last resort, other materials such as sand may be used. Avoid using these materials as they create a large amount of contaminated waste.
  - For a solids spill, dust suppression measures may be required if dust is an issue.

#### Clean-up the Spill

Once the source of the spill has been controlled and the spill contained (immediate threat to the environment has been minimised) the rest of the spill will need to be cleaned-up.

- oil/fuel spills, continue to use absorbent materials from oil spill kits around site. Used and contaminated absorbent materials should be collected in either 220L drums or in lined skip bins, depending on the size of the clean-up. This applies for spills on sealed and gravel areas
- For mineral concentrate spills scrape up the spillage, use contractor to suck up the product or wash down the affected area. Do not let wash waters enter stormwater drains and contact the Environmental Team to request the most applicable disposal method. Where possible, the material shall be recovered and recycled. This may apply to:
  - a. ore concentrate
  - b. sulphur granules
  - c. chemicals
  - d. waste oil / grease

If material cannot be recycled, advice should be sought from the Environment Department on appropriate disposal methods to ensure compliance with the Environment Protection Act

#### Restock Kits

Any personnel who use spill response equipment must ensure it is appropriately replenished and returned to its storage position prior to resuming work.

#### Reporting

Staff member who was notified of the spill is to complete an incident report with the Environment Team

## Spill Hierarchy

The spill hierarchy depends on the risks of the spilt material that depends on the type of substance spilt as well as the volume of the spill. The following presents guidance on describing a category for the spill.

### Minor Spills

A minor spill is typically:

- easily contained and so does not pose a risk to human health or the environment;
- can be cleaned up by an individual or within the work area using spill response equipment; Note that:
- Providing there is total clean-up of a spill on a sealed area it can be reported as a near miss; and
- If the spill occurs on an unsealed area, it is an emission to land and groundwater and must be reported as an incident.

Oil contamination of unsealed areas should be avoided. Spillage on an unsealed area is an environmental incident as it may contaminate soil, groundwater and stormwater. Spillage on a sealed area can be banded, recovered and restricted to a temporary hazard.

### Significant Spills

A significant spill may:

- Not be readily contained by an individual or within the work area using the available spill response equipment;
- May require the involvement of the site's team members from other work areas.
- Likely to endanger safety, result in pollution or disrupt operations;
- Is an incident and requires reporting and investigation by the Environment Team.

### Major Spills

A major spill typically requires:

- Evacuation of personnel and the immediate involvement of the Emergency Response Team

Examples of major spills are:

- Oil spill into stormwater system or directly into the ocean;
- Flammable materials that are uncontained;
- Hazardous gases that are filling a confined space;

## **CONTAMINATED LAND**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to contaminated ground for inclusion in the Environmental Management Plan.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site/Location Manager**

- Overall responsibility for prevention and control of known contaminated land issues on site
- Develop section of the Environmental Management Plan to include prevention and control of known land contamination
- Liaise with the Environmental Manager for all contaminated land issues

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan regarding the prevention and control of land contamination issues
- Ensure all staff comply with the contaminated land guidelines

### **PROCEDURES**

#### **Operational Control Guidelines**

1. Any areas of contaminated land must be identified from the site investigation data and contract documents so that its treatment and/or disposal can be managed.
2. If additional sampling or testing is required, this must be identified prior to the commencement of any works.
3. All operations involving contaminated land must be clearly identified and specific risk assessments and method statements must be prepared.
4. If contaminated materials are stored on site, the method of containment must prevent any escape of dust, leachate or other substances.
5. Disposal of contaminated materials off site must be to licensed sites and in accordance with the Duty of Care.
6. All permanent and non-permanent employees, including sub-contractors, must be made aware of their responsibilities to ensure that contaminated land is unable to cause further pollution.

7. In the event that contaminated land causes further pollution then the Emergency Control Procedures stated below must be followed.

### **Emergency Control Procedures**

1. When dealing with known contaminated land and 'run-off' is becoming a problem the Emergency Control Procedures for water pollution must be followed.
2. When dealing with known contaminated land and dust generation is becoming a problem the Emergency Control Procedures for air must be followed.
3. In addition to this all operatives in the area must be issued with dust masks to prevent ingestion of the contaminated materials.
4. Stop work immediately, seal off the area, and report to the Site Manager in the event that one or more of the following are found:
  - Discoloured or oily soil (chemical or oil residues)
  - The soil has a fibrous texture (asbestos)
  - Presence of foreign objects (chemical/oil containers)
  - Evidence of underground structures and storage tanks
  - Existence of waste pits
  - Old drain runs and contamination within building and tanks
5. The contaminated materials must be tested at an approved laboratory to ascertain what hazards may be presented by the substance.
6. Following the receipt of the laboratory results a specific method statement and risk assessment must be prepared to dispose of/deal with the material.



## **ECOLOGY, ARCHAEOLOGY AND CULTURAL HERITAGE**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to ecology, archaeology, and cultural heritage for inclusion in a Specific Environmental Management Plan.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site Manager**

- Overall responsibility for ecology, archaeology, and cultural heritage on site
- Develop section of the Environmental Management Plan to include ecology, archaeology, and cultural heritage
- Ensure all sub-contractors comply with the ecology, archaeology, and cultural heritage guidelines
- Liaise with the Environmental Manager on all ecology, archaeology, and cultural heritage issues

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan ecology, archaeology, and cultural heritage issues
- Ensure all staff comply with the ecology, archaeology, and cultural heritage guidelines

### **PROCEDURES**

#### **Operational Control Guidelines**

1. Any contractual requirements for the preservation, monitoring and management of ecology, archaeology and cultural heritage issues must be prior to the commencement of any works.
2. All areas where ecological, archaeological and cultural heritage issues exist should be highlighted in the Environmental Management Plan.
3. Specific risk assessments and method statements must be completed for all operations that may impact on sensitive parts of the site. This is to ensure that all such operations are properly managed and controlled.
4. The Site Manager is responsible for liaising with English Heritage and other interested parties to ensure that no issues are overlooked when planning potentially disruptive works.
5. Strict controls shall be implemented where necessary to ensure that any persistent vegetation such as Japanese Knotweed is not allowed to spread around or off of the site.

6. All permanent and non-permanent employees, including sub-contractors, will be made aware of their responsibilities to ensure that damage to ecology, archaeology and cultural heritage is minimised.
7. In the event that damage to ecology, archaeology and cultural heritage occurs then the Emergency Control Procedures below should be followed.

### **Emergency Control Procedures**

1. In the event that damage to any ecology, archaeology and cultural heritage occurs work must be stopped immediately.
2. The incident must be reported to the Site Manager.
3. The area should then be protected using Heras type fencing or similar.
4. Specialist advice should be sought from relevant organisations such as English Nature or English Heritage.
5. The Environmental Manager must be notified.
6. Special consent may be required before work can recommence from the relevant authority.
7. The reason for the problem occurring must be investigated and any changes made to future operations and programmes.
8. In the event that a serious incident occurs, contact the company's Environmental Manager.

## **NOISE AND VIBRATION**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to noise and vibration for inclusion in a Specific Environmental Management Plan.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site Manager**

- Overall responsibility for control of noise and vibration on site
- Develop section of the Environmental Management Plan to include prevention and control noise and vibration
- Ensure all sub-contractors abide by noise and vibration guidelines
- Liaise with the Environmental Manager for all noise and vibration issues

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan for environmental noise and vibration issues
- Ensure all staff comply with the noise and vibration guidelines

### **PROCEDURES**

#### **Operational Control Guidelines**

1. Requirements regarding the control of noise and vibration levels should be identified so that the appropriate control measures can be implemented.
2. The company's environmental policy and procedures will be taken into account when selecting plant and equipment and when developing safe systems of work.
3. Where it has been identified that buildings and services may be affected by noise and vibration, all necessary control measures are to be highlighted within applicable safe systems of work.
4. In sensitive areas, such as urban and commercial districts, liaison with the Environmental Health Officer will be needed to ensure that noise and vibration levels are maintained within permissible levels.
5. Noise emissions should be regularly monitored and recorded as deemed appropriate.
6. Where necessary vibration will be monitored to ensure that no structural damage is being caused to adjacent buildings and services.

7. Local residents and businesses are to be kept informed of when activities producing excessive noise and vibration are to take place.
8. All operations should be sequenced, where appropriate, to minimise the generation of noise and vibration, and where practical, plant and material stockpiles should be located to absorb noise emissions.
9. Where appropriate, prior consent will be sought from the local authority under Section 61 of the Control of Pollution Act 1974.
10. All employees, sub-contractors and suppliers will be made aware of their responsibilities and duties to ensure that noise and vibration generated by them is correctly managed and controlled.
11. In the event that noise and vibration emissions exceed permissible levels, then the following Emergency Control Procedures are to be followed.

#### **Emergency Control Procedures**

1. In the event of noise and vibration limits being exceeded the work or activity causing the noise/vibration is to be stopped.
2. Where appropriate plant is to be re-orientated to re-direct emissions away from sensitive receptors.
3. Where appropriate material is to be stockpiled to provide a noise barrier to absorb noise emissions.
4. Where appropriate erect additional noise barriers.
5. If these steps are unsuccessful in reducing emissions to an acceptable level then working practices and arrangements will be changed accordingly.
6. Monitoring shall take place throughout the operation to ensure compliance.

## **STATUTORY NUISANCE**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to statutory nuisance for inclusion in a Specific Environmental Management Plan.

### **DEFINITION**

Although there is no legal definition of a statutory nuisance, for action to be taken, the nuisance must, or be likely to be prejudicial to a persons health, or interfere with a persons legitimate use and enjoyment of land. This particularly applies to nuisance to neighbours in their homes, offices and gardens.

A statutory nuisance could arise from the poor state of the company's premises or sites, or from any noise, smoke, fumes, gases, dust, steam, smell, effluvia, the keeping of animals', deposits and accumulations of refuse and/or other material, and other discharges from company premises.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site Manager**

- Overall responsibility for control of statutory nuisance on site
- Develop section of the Environmental Management Plan to include prevention and control of statutory nuisance
- Ensure all sub-contractors abide by statutory nuisance guidelines
- Liaise with the Environmental Manager for all statutory nuisance issues

#### **Environmental Manager**

- Assist Site Managers in the development of the Environmental Management Plan for statutory nuisance issues
- Ensure all staff comply with the statutory nuisance guidelines

## **PROCEDURES**

### **Operational Control Guidelines**

1. The procedures for air pollution, contaminated land, noise and vibration, and water pollution should be followed to prevent any statutory nuisance in these forms.
2. If the site is located adjacent to residential areas then any lighting that is required is to be located to minimise disruption through glare or light pollution.

3. All complaints from local residents are to be collated and where appropriate procedures developed to prevent any recurrence.
4. In the event of an incident involving statutory nuisance the Emergency Control Procedures below must be followed.

#### **Emergency Control Procedures**

1. Should any incident surrounding statutory nuisance occur, the appropriate operational procedures, as identified above, must be followed.
2. All complaints shall be recorded and the Environmental Manager shall be notified.
3. Where problems occur regarding site lighting then the lighting shall be relocated to reduce the impact upon the surrounding residents and neighbours.

## **TRAFFIC MANAGEMENT**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to traffic management for inclusion in a Specific Environmental Management Plan.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site Manager**

- Overall responsibility for traffic management on site and for liaising with the local highway authorities
- Develop the Environmental Management Plan to include traffic management proposals
- Ensure all sub-contractors abide by traffic management requirements
- Liaise with the Environmental Manager for all traffic management issues

#### **Environmental Manager**

- Assist Site Managers in the development of traffic management proposals for the Environmental Management Plan
- Ensure all staff comply with the statutory nuisance guidelines

### **PROCEDURES**

#### **Operational Control Guidelines**

1. All traffic management issues identified in the contract documents must be incorporated into the Environmental Management Plan.
2. Where appropriate, arrangements for the delivery of materials should take place outside peak hours.
3. All access roads should be regularly monitored for damage and deposition of mud and debris, where mud and debris are found to be a problem, all debris should be quickly removed and the roads kept clean and tidy.
4. All plant should be regularly serviced to ensure that it does not cause excessive pollution and operates safely and efficiently.
5. In the event that a traffic management problem occurs the Emergency Control Procedures below should be followed.

## **Emergency Control Procedures**

1. In the event that the increased numbers of traffic movements adjacent to the site cause problems with congestion, road conditions or noise, then measures should be implemented to minimise them.
2. Where congestion is occurring at the beginning and end of the day, the use of flexible working hours and staggered starting times should be considered.
3. Where excess mud and debris is being deposited on local roads around the site, the incorporation of wheel washes and use of road sweepers should be considered.



## **WASTE MANAGEMENT**

### **PURPOSE**

The purpose of this procedure is to provide guidance and assistance with the development and production of specific procedures with regards to waste management for inclusion in a Specific Environmental Management Plan.

### **SCOPE**

This procedure applies to all employees and operational activities. The responsibilities for implementing the procedure are outlined below.

#### **Site Manager**

- Overall responsibility for waste management on site
- Develop section of the Environmental Management Plan to include the management of waste, including the segregation of waste and the use of recycling initiatives
- Ensure all sub-contractors abide by waste management guidelines
- Liaise with the Environmental Manager for all waste management issues

#### **Environmental Manager**

- Assist Site Managers in the development of waste management proposals for the Environmental Management Plan
- Ensure all staff comply with the waste management guidelines

### **PROCEDURES**

#### **Office Waste Guidelines**

1. All consumables and office supplies are to be used conservatively, including the recycling and reuse of supplies where practical.
2. Company paper is only to be used for business purposes and waste paper should be recycled rather than disposed of.
3. The use of double-sided copying and printing should be made wherever practical.
4. Scrap paper will be reused for draft printing whenever possible.
5. Office paper supplies will be discarded separately into segregated and designated recycling bins. All cardboard materials will be discarded separately into respective segregated bins. All other rubbish will be discarded in the normal manner.

#### **OPERATIONAL CONTROL GUIDELINES**

1. All work shall be carefully considered and implemented to minimise the generation of waste.

2. Where it has been identified that wastes are to be produced, or potentially produced, by a new or activity, this will be clearly identified prior to the commencement of the work.
3. Specialist disposal requirements including any Waste Management License issues will be identified prior to commencement.
4. All employees, including sub-contractors will be requested to identify the types of waste that can be reduced, reused, or re-cycled on-site or off-site.
5. All employees, suppliers and sub-contractors will be made aware of their responsibilities to ensure the correct disposal of waste.
6. Where the production of hazardous wastes is envisaged, the Site Manager will liaise with the Environmental Manager and the appropriate Environment Agency office to determine the most appropriate method of disposal.
7. All sites producing hazardous waste must be licensed with the Environment Agency.
8. Waste disposal contractors must possess the appropriate license to dispose of the waste from site. The site manager should periodically check the waste contractor's current license.
9. All waste disposal operations shall comply with the Duty of Care. A Waste Transfer Note/Consignment Notice will accompany all waste transfers. The Waste Transfer Note must be retained for a minimum of three years.
10. The storage requirements for wastes are to be identified to allow for the segregation of the waste and the prevention of odours, water pollution and the cross contamination of materials.
11. In the event of the escape of waste the Emergency Control Procedures below must be followed.

## **Emergency Control Procedures**

### **Liquid Waste**

1. In the event of liquid waste escaping the site manager is to be notified.
2. The Site Manager is to notify the Environmental Manager and the appropriate Environment Agency office.
3. Stop the flow of pollution using earth, sand or polythene and divert away from drains and watercourses.
4. Deploy spill kits as necessary to contain and absorb the spill.
5. Contaminated sand, earth or granules must be disposed of as contaminated material

6. The reasons and cause of the escape must be thoroughly investigated, and recommendations made to prevent a reoccurrence.

### **Solid Waste**

1. In the event of solid waste escaping the Site Manager is to be notified.
2. The waste that has escaped must be collected and placed into a secure skip.
3. Depending on the hazard presented by the material, specific personal protective equipment may be required.
4. The reasons and cause of the escape must be thoroughly investigated, and recommendations made to prevent a reoccurrence.

### **Odours from Waste**

1. In the event that odours become a problem from waste storage, the skips must be emptied immediately.
2. If similar waste is likely, then covered skips must be used and emptied regularly.